

Załącznik nr 4.2 Tabela robót ziemnych - drogi nr 5

ROBOTY ZIEMNE DR-5								
Poprzeczka	Km	Odległości	ROBOTY ZIEMNE				HUMUS WYKOP	
			Pow. [m2]		Obj. [m3]		Szer. [m]	Pow. [m2]
		[m]	W	Ngr	W	Ngr	s	p
PP	0+000.00	—	2.40	4.43	—	—	5.76	—
P2-1	0+015.00	15.00	2.40	4.43	36.00	66.45	5.76	86.40
P2-2	0+050.00	35.00	2.34	1.57	82.95	105.00	6.41	212.98
P2-3	0+100.00	50.00	2.40	3.93	118.50	137.50	6.12	313.25
P2-4	0+150.00	50.00	2.27	2.91	116.75	171.00	5.39	287.75
P2-5	0+200.00	50.00	2.20	2.68	111.75	139.75	5.46	271.25
P2-6	0+250.00	50.00	2.20	2.24	110.00	123.00	5.46	273.00
P2-7	0+300.00	50.00	2.18	2.11	109.50	108.75	5.47	273.25
P2-8	0+350.00	50.00	2.19	1.99	109.25	102.50	5.48	273.75
P2-9	0+400.00	50.00	2.20	1.77	109.75	94.00	5.49	274.25
P2-10	0+450.00	50.00	2.40	3.46	115.00	130.75	5.91	285.00
P2-11	0+500.00	50.00	3.45	2.24	146.25	142.50	7.99	347.50
P2-12	0+550.00	50.00	2.24	3.05	142.25	132.25	5.40	334.75
P2-13	0+600.00	50.00	2.30	3.41	113.50	161.50	5.43	270.75
P2-14	0+650.00	50.00	2.26	3.62	114.00	175.75	5.49	273.00
P2-15	0+700.00	50.00	2.33	3.31	114.75	173.25	5.74	280.75
P2-16	0+750.00	50.00	2.13	2.36	111.50	141.75	5.45	279.75
P2-17	0+800.00	50.00	2.30	2.70	110.75	126.50	5.80	281.25
P2-18	0+850.00	50.00	2.40	2.70	117.50	135.00	6.18	299.50
P2-19	0+900.00	50.00	2.34	2.72	118.50	135.50	5.90	302.00
P2-20	0+950.00	50.00	2.40	2.91	118.50	140.75	6.10	300.00
PP	0+966.00	16.00	2.40	2.91	38.40	46.56	6.10	97.60
					1	1	γ	1
					2265	2690	SUMA	7391