

Załącznik nr 4.1 Tabela robót ziemnych - drogi nr 2

ROBOTY ZIEMNE DR-2										
Poprzeczka	Km	Odległości	ROBOTY ZIEMNE				HUMUS WYKOP		PLANTOWANIE	
			Pow. [m ²]		Obj. [m ³]		Szer. [m]	Pow. [m ²]	Szer. [m]	Pow. [m ²]
		[m]	W	Ngr	W	Ngr	s	p	s	p
PP	0+000.00	—	0.00	0.83	—	—	0.00	—		—
P1-1	0+015.52	15.52	0.00	0.83	0.00	12.88	0.00	0.00		0.00
P1-2	0+050.00	34.48	0.03	0.44	0.52	21.89	0.86	14.83		0.00
P1-3	0+100.00	50.00	0.00	0.82	0.75	31.50	1.60	61.50		0.00
P1-4	0+150.00	50.00	0.45	0.84	11.25	41.50	1.87	86.75		0.00
P1-5	0+200.00	50.00	0.20	0.69	16.25	38.25	1.84	92.75		0.00
P1-6	0+250.00	50.00	0.78	0.99	24.50	42.00	1.93	94.25		0.00
P1-7	0+300.00	50.00	0.42	0.86	30.00	46.25	1.11	76.00		0.00
P1-8	0+350.00	50.00	0.53	1.10	23.75	49.00	1.02	53.25		0.00
P1-9	0+400.00	50.00	0.29	1.43	20.50	63.25	0.82	46.00		0.00
P1-10	0+450.00	50.00	1.05	1.02	33.50	61.25	1.43	56.25		0.00
P1-11	0+500.00	50.00	0.12	1.57	29.25	64.75	0.92	58.75		0.00
P1-12	0+550.00	50.00	0.52	1.10	16.00	66.75	2.08	75.00		0.00
P1-13	0+600.00	50.00	0.37	1.35	22.25	61.25	2.07	103.75		0.00
P1-14	0+650.00	50.00	0.09	1.08	11.50	60.75	1.29	84.00		0.00
P1-15	0+668.00	18.00	0.25	0.40	3.06	13.32	1.36	23.85		0.00
PP	0+678.20	10.20	0.25	0.40	2.55	4.08	1.36	13.87		0.00
					1	1	γ	1	γ	1
					246	679	SUMA	941	SUMA	0